



Cartons for this Play Set:

1 63007-421	Lexington Box 1 (Hardware)
1 63007-422	Lexington Box 2
1 63007-423	Lexington Box 3
1 63007-424	Lexington Tent (Hdwre & Instr)
1 SH946-102	Access Ladder 5ft.
1 AG942-400	Access Handles (Hdwre & Instr)
1 63058-202	4 Position Swing Beam
1 63059-212	7ft Beam Legs (Hdwre & Instr)
1 31820-102	Swing Mount
1 50546-777	3 Swings, 1 Trapeze
1 8364-400	10 ft Scoop Slide, Green
1 AH201-102Q	Rock Wall (Hdwre & Instr)
1 SD204-102Q	Lex. Picnic Table (Hdwre & Instr)

Dimensions of assembled package:
20' 0" wide x 15' 4" deep x 10' 7" tall

The components of this gym can be combined with others to create different play sets. This is the best order of assembly to create this specific set.

Read this sheet and all instructions included with the different parts before assembly.

See the Instructions and Owner's Manual included in carton 63007-424 for important safety information.



- Start by assembling the Lexington tower. Instructions and hardware are in the cartons noted above right.
- Wait to install the Access Ladder, Slide, and Wall Slats until after the rest of the play set is complete.
- On step 19 be sure to install the swing mount on the side shown above.
- Lex step 20. Do not install the safety rail. It will be used for the picnic table.
- Install the Picnic Table (SD204-102Q).
- Install the swing beam. Instructions and hardware are in the 7' Swing Beam Leg carton (63059-212).
- Assemble the Rock Climbing Wall (AH201-102Q). When mounting to the gym, set the rock wall and access ladder in place to determine spacing.
- Secure the Access Ladder (SH946-102) using the method shown in step 18 of the Lexington instructions.
- Mount the Access Ladder Handles (AG942-400) to the ladder.
- Install the slide mount and slide using the method shown in steps 26 and 27 of the Lexington instructions
- Install the wall slats in the positions shown above, using the methods from the Lexington Instructions. Gaps must be narrower than 3-1/2" or wider than 9" to prevent potential head entrapment.
- Mount the hand grips to the entrance wall slats.
- Double-check all fasteners are secure and all recessed hardware is covered by hole caps.