Creative Plaything/®

CHILDHOOD STARTS HERE

LEXI9WPP4 Lexington Premium Pack 4

Cartons for this Play Set:

3

1

- 63007-421Lexington Box 1 (Hardware)63007-422Lexington Box 2
- 63007-423 Lexington Box 3
- 63007-445 Lexington Roof (Hdwre & Instr)
- SH946-102 Access Ladder, 5ft
- 63058-202 4 Position Swing Beam
- 63060-222 9ft Swing Beam Legs (Hdwre & Instr)
- 32404-102 Wall Slat 5/4 x 6 x 31-1/2"
- 50546-777 3 Swings, 1 Trapeze
- 8364-400 10 ft Scoop Slide, Green

Dimensions of assembled package: 17' 5" wide x 15' 4" deep x 11' 6" tall

The components of this gym can be combined with others to create different play sets. This is the best order of assembly to create this specific set.

Read this sheet and all instructions included with the different parts before assembly.

See the Instructions and Owner's Manual included in carton 63007-445 for important safety information.

- Start by assembling the Lexington tower. Instructions and hardware are in the cartons noted above right.
- Wait to install the Access Ladder, Slide, and Wall Slats until after the rest of the play set is complete.
- On step 21 be sure to install the swing mount on the side shown above.
- Install the swing beam. Instructions and hardware are in the 9' Swing Beam Leg carton (63060-222).
- Set the ladder and slide as shown above. Check spacing.
- Fasten access brackets to the inside of the ladder rails. Secure the access ladder using the method shown in step 20 of the Lexington instructions.

- Install the slide mount and slide using the method shown in steps 28 and 29 of the Lexington instructions
- Install the wall slats in the positions shown above, using the methods from the Lexington Instructions. Gaps must be narrower than 3-1/2" or wider than 9" to prevent potential head entrapment.
- Mount one hand grip to the entrance wall slat between the ladder and the slide. Mount the other hand grip to the adjacent post at the same height, using 1/4 x 1-1/2" lag screws and 1/4" flat washers. Drill 3/16" diameter pilot holes for the lag screws.
- Double-check all fasteners are secure and all recessed hardware is covered by hole caps.

LEXINGTON PREMIUM PACK 4