## Creative Playthings

## CHILDHOOD STARTS HERE

## LEXI9WPP5 LEXINGTON PREMIUM PACK 5

## **Cartons for this Play Set:**

1 63007-421 Lexington Box 1 (Hardware)

63007-422 Lexington Box 2 63007-423 Lexington Box 3

1 63007-445 Lexington Wood Roof (Hdwre & Instr)

1 SH946-102 Access Ladder, 5ft

1 AG942-400 Access Ladder Handles (Hdwre & Instr)

1 63058-202 4 Position Swing Beam

1 63060-222 Swing Beam Legs 9ft (Hdwre & Instr)

50546-777 3 Swings, 1 Trapeze 8364-400 10 ft Scoop Slide

SD204-102Q Lexington Picnic Table (Hdwre & Instr)

AH201-102Q Rock Climbing Wall (Hdwre & Instr)

Dimensions of assembled package: 20' 0" wide x 15' 4"deep x 11' 6" tall



The components of this gym can be combined with others to create different play sets. This is the best order of assembly to create this specific set.

Read this sheet and all instructions included with the different parts before assembly.

See the Instructions and Owner's Manual included in carton 63007-445 for important safety information.



- Start by assembling the Lexington tower. Instructions and hardware are in the cartons noted above right.
- Wait to install the Access Ladder, Slide, and Wall Slats until after the rest of the play set is complete.
- On step 21 be sure to install the swing mount on the side shown above.
- Skip step 22. Do not install the safety rail. It will be used on the picnic table.
- Install the swing beam. Instructions and hardware are in the 9' Swing Beam Leg Carton (63060-222).
- Install the Picnic Table (SD204-102Q).
- Install the Rock Climbing Wall (AH201-102Q) in the position shown.

- Secure the Access Ladder (SH946-102) next to the Rock Climber using the method shown in step 20 of the Lexington instructions.
- Fasten the Access Ladder Handles (AG942-400).
- Install the slide mount and slide using the method shown in steps 28 and 29 of the Lexington instructions
- Install the wall slats in the positions shown above, using the methods from the Lexington Instructions. Gaps must be narrower than 3-1/2" or wider than 9" to prevent potential head entrapment.
- · Mount the hand grips to the entrance wall slats.
- Double-check all fasteners are secure and all recessed hardware is covered by hole caps.

**LEXINGTON PREMIUM PACK 5**