



The components of this gym can be combined with others to create different play sets. This is the best order of assembly to create this specific set.

Read this sheet and all instructions included with the different parts before assembly.

See the Instructions and Owner's Manual included in carton 63007-445 for important safety information.

Dimensions of assembled package:  
19' 7" wide x 14' 6" deep x 11' 6" tall

### Cartons for this Play Set:

1	63007-421	Lexington Box 1 (Hardware)
1	63007-422	Lexington Box 2
1	63007-423	Lexington Box 3
1	63007-445	Lexington Wood Roof (Hdwre & Instr)
1	SH946-102	Access Ladder, 5ft
1	AG942-400	Acc. Ladder Handles (Hdwre & Instr)
1	63058-202	4 Position Swing Beam
1	63060-222	9ft Swing Beam Legs (Hdwre & Instr)
1	50546-777	3 Swings, 1 Trapeze
1	8364-400	10 ft Scoop Slide
1	SD204-102Q	Lex Picnic Table (Hdwre & Instr)
1	AH201-102Q	Rock Climbing Wall (Hdwre & Instr)
1	63079-102	Monkey Bars (Hdwre & Instr)



- Start by assembling the Lexington tower. Instructions and hardware are in the cartons noted at left.
- Wait to install the Access Ladder, Slide, and Wall Slats until after the rest of the play set is complete.
- Lexington step 21. No Swing Mount is needed.
- Lexington step 22. Do not install the safety rail. It will be used for the picnic table.
- Install the swing beam. Instructions and hardware are in the 9' Swing Beam Leg Carton (63060-222).
- Install the Picnic Table (SD204-102Q).
- Install the Monkey Bars (63079-102). Mount one side directly to the corner post as shown above.
- Mount the Rock Climbing Wall (AH201-102Q) in the position shown.
- Secure the access ladder next to the rock wall using the method shown in step 20 of the Lexington instructions.
- Mount the Access Ladder Handles (AG942-400).
- Install the slide mount and slide using the method shown in steps 28 and 29 of the Lexington instructions.
- Install wall slats in the positions shown above, using the methods from the Lexington instructions. Gaps must be narrower than 3-1/2" or wider than 9" to prevent potential head entrapment.
- Mount the hand grips to the entrance wall slats.
- Double-check all fasteners are secure and all recessed hardware is covered by hole caps.