

Dimensions of assembled package:
13' 2" wide x 23' 5" deep x 11' 6" tall



The components of this gym can be combined with others to create different play sets. This is the best order of assembly to create this specific set.

Read this sheet and all instructions included with the different parts before assembly.

See the Instructions and Owner's Manual included in carton 63089-116 for important safety information.

Cartons for this Play Set:

1	63089-116	Norfolk II Box 1 (Hdwre & Instr)
1	63089-216	Norfolk II Box 2
1	63089-316	Norfolk II Box 3
1	63089-416	Norfolk II Roof
1	63089-606	Norfolk II Cargo Net
1	63045-505	Norfolk Tire Swing (Hardware)
1	63058-202	4 Position Swing Beam
1	63076-303	9 ft Beam Legs (Hdwre & Instr)

1	50546-777	3 Swings, 1 Trapeze
1	15166-400	10 ft. Super Wave Slide
1	SM964-402	Gable Fans (Hdwre & Instr)
1	SM963-402	Dormer (Hdwre & Instr)
1	63079-102	Monkey Bars (Hdwre & Instr)
1	AS974-500	Chalkboard Panel (Hdwre & Instr)
1	50514-100	Tic Tac Toe (Hdwre & Instr)
1	AG942-400	Access Handles (Hdwre & Instr)
1	AG943-400	Slide Handle (Hdwre & Instr)

- Assemble the Norfolk tower. Instructions and hardware are in the cartons noted above.
- Wait to install wall slats and slide until later.
- Once the tower is assembled, assemble and install the Dormer (SM963-402). The slide and beam will limit ladder access if installed later.
- Install the Gable Fans (SM964-402).
- Install the Monkey Bars (63079-102). Mount one side directly to the corner post as shown above.
- Install the slide mount and Super Wave Slide (15166-400) using the method shown in steps 37 and 38 of the Norfolk instructions.
- Mount the Slide Handle (AG943-400) above the slide.
- Mount the Access Handles (AG942-400) on each side of the plastic steps.
- Install the swing beam. Mount the beam to the inside of the back post as shown above. Instructions and hardware are in the 9 ft Swing Beam Leg carton (63076-303).
- 9 ft beam step 1. Prepare to mount the beam to the post

by drilling from the inside of the post as shown below. Drill a 3/8" diameter hole through the post 2-1/4" from the top. Drill 7/16" diameter holes through the post at 6-3/8" and 14-3/8" from the top.

- Complete installation of the beam. Ignore the notes regarding the Norfolk gym on the last page of the beam instructions. The notes are for a different Norfolk model.
- Install the Tic-Tac-Toe (50514-100) and Chalkboard (AS974-500) along with wall slats across the back of the gym as shown above. Make sure no gaps are larger than 3-1/2" to prevent potential head entrapment.
- Double-check all fasteners are secure and all recessed hardware is covered by hole caps.

